# BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/RD/WORK_INDENT18545/CALL-2

## APPROVED SCHEDULE - B

**EE/BTP/BBMP/E-PMT/03/2015-16, Date: 22.01.2016**

**Improvements to Roads and Drains at Akashavani Layout Dasarahalli in Ward No. 6 Byatarayanapura Sub Division**

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of CHENNAKRISHNA P | | |
|---|---|---|---|---|---|---|
| | | | | In Figures | | In Words |
| 1 | 117.07 | KSRB 2-2.1 : earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in Hard soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification, No, KBS 2.1(a) / 2.3.5, No. 5/ Item No. 2.4/ PWD SR 2015-16 | Cum | 230.0 | 26926.10 | Rupees Two Hundred Thirty Only |
| 2 | 21.89 | KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M 1:4:8 withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2, No. 12/ Item No. 4.3/ PWD SR 2015-16 | Cum | 4900.0 | 107261.00 | Rupees Four Thousand Nine Hundred Only |
| 3 | 7.02 | KSRB 5.2.3 Providing and constructing granite / trap / basalt Size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 Page No. 23/ Item No. 5.6/ PWD SR 2015-16 | cum | 4000.0 | 28080.00 | Rupees Four Thousand Only |
| 4 | 5.85 | KSRB 5.3-3 Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5-1.13 Page No. 23/ Item No. 5.9/ PWD SR 2015-16 | Sqm | 4800.0 | 28080.00 | Rupees Four Thousand Eight Hundred Only |
| 5 | 658.5 | KSRB 4-6.7 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1 m in depth including cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 Page No. 16/ Item No. 4.34/ PWD SR 2015-16 | Sqm | 239.0 | 157381.50 | Rupees Two Hundred Thirty Nine Only |
| 6 | 2.08 | KSRB 4-1.7 : : Providing and laying in position plain cement concrete of mix 1:3:6 withOPC cement @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @0.56cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2/P No. 13/ Item No. 4.7/ PWD SR 2015-16 | cum | 5200.0 | 10816.00 | Rupees Five Thousand Two Hundred Only |
| 7 | 13 | masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. Page No. 109/ Item No. 15.1/ PWD SR 2015-16 | Sqm | 85.0 | 1105.00 | Rupees Eighty Five Only |

P. Channa Krishna

H.V.
ಸ.ಅ. (ಬಾ.ಪ) 24/5/16

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of CHENNAKRISHNA P | | |
|---|---|---|---|---|---|---|
| | | | | In Figures | | In Words |
| 8 | 77.29 | KSRB 4.2.2 : Providing and laying in position plain cement concrete of mix M20 withOPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum with superplastesisre @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor | Cum | 5850.0 | 452146.50 | Rupees Five Thousand Eight Hundred Fifty Only |
| 9 | 5.8 | KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete | Qtl | 67000.0 | 388600.00 | Rupees Sixty Seven Thousand Only |
| 10 | 117.07 | Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km ( Page No.123, | Cum | 55.0 | 6438.85 | Rupees Fifty Five Only |
| | | | | | **1206834.95** | |

P. Chennakrishna

**Signature of the Contractor**

**Executive Engineer**
**Byarayanapura Division**
**BBMP, Bangalore - 92**

24/3/16

24/03